

ITEM 560

MAINTENANCE AND CLEANUP OF THE PROJECT SITE

- 560.1 Description. This item shall govern for the maintenance and cleanup of the jobsite both during the term of the construction and at the end of construction.
- 560.2 General Requirements. The Contractor is required to remove from the job site all trash, excess materials, etc., accumulated as a result of and during this work.
- At such time (daily or weekly) as directed by the Engineer, the Contractor shall remove any debris, trash or excess material off the site. He shall make every effort to keep the site in a neat, presentable condition, at all times.
- In addition, at the end of each month, the entire construction site shall be generally cleaned and all trash and material over the length of the site shall be removed off site to the complete satisfaction of the Engineer.
- After the construction work has been completed, the Contractor shall remove all debris, trash, excess materials, forms, stakes, empty sacks etc. from the site and leave the site with a neat appearance. All excavation shall be backfilled and all excess excavated material shall be disposed of off the site of the work.
- 560.3 Measurement and Payment. There shall be no separate payment for this item.

END OF ITEM 560